

Water Testing at Marie Katzenbach School for the Deaf for 2018 was done by Leco Laboratory. Here is a summary of the results:

These samples are "first draw" samples, which means the water has been immobile for at least six hours in the plumbing.

1st draw Maximum Contaminant Levels (MCLs):

Lead = 15 mg/L

Sample Location	Results
ELMS Annex Art Room front sink	0.020 mg/L
HS Art room 14 Bathroom sink	0.019 mg/L
Residence Room 8 & 9	0.042 mg/L

These failures may be due to a number of situations. Corrosion of plumbing and fixtures are the main culprits. Most times the problems can be rectified by replacing the faucets at the problem location.

\*Information provided by Donald B. Lilley, Leco Laboratory  
NJDEP Certified Lab No. 11006  
3123 Klockner Road, Trenton, NJ 08690  
Telephone: 609.588.0011